




1. Introduction into het project Factsheet Iast in a chain of 30 measures in The Netherlands unique and extensive: 7,5 km deepening of summerbed 20 km dikes Reevediep project area Reevediep: 570 ha (> 350 ha nature development) 6 flood plains ground work: 6 million m³ (incl. 2 million m³ river sand) 41 cm high water level reduction (near the city of Zwolle) max. capacity Reevediep: 730 m³/s (25 % discharge of river IJssel, 72 cm high water level reduction near the inlet (30 cm near Zwolle)) flood protected area: Zwolle, Hattem, Elburg, Kampen, Zwartwaterland implementation: 2015 – 2019 (phase 1), 2017 – 2022 (phase 2)






































Project process: 5 periods

- 1. Initial phase: Programme Room for the River (start ca. 200
- 2. National pilot project "integrated area development": sho intensive period of public participation which resulted in a broady supported masterplan (2005-2007)
- 3. Long, turbulent formal phase (2007-2015), which culmina
- 4. A combined implementation of river bypass and deepenin the summerbed (phase 1: 2015-2019)
- 5. Phase 2 (Dutch Delta Programme): 2017-2022

10 important moments

- 2004: Regional Advice Programme Room for the River
 - bypass versus deepening of summerbed / "exchange decision
 2006: Masterplan Area Development "IJsseldelta-Zuid"
- - → intensive participation / adaptation railway + motorway
- 2007: start voluntary purchase of land + property
 - → ± 95% acquired voluntarily
- 2008: Review of Regional land use plans (Overijssel + Flevoland)
- 2009: Decision national government: combine deepening of summerbed bypass
 - → partner projects instead of competitors
 - → after advice Delta Commission + enhanced hydraulic targe
- 2010: Gentlemen's agreement + start 2 "plan studies"
- 2011: Results "plan studies"
 - → deepening summerbed can't be fully implemented
- 2012: Decision after reviewed "plan studies ": "shortened" deepening of summerbed + bypass
- 2013: Start legal procedures plans, permits, licences + start tender
- 10. 2014/2015: Procedures Council of State, expropriation, contract with contrator (Isala Delta)

